
CHAPTER 8

CONCRETE STRUCTURES AND FOUNDATIONS¹

FOREWORD

The material in this chapter is written with regard to typical North American Railroad Concrete Structures and Foundations and other structures mentioned herein with

- Standard Gage Track,
- Normal North American passenger and freight equipment, and
- Speeds of freight trains up to 80 mph and passenger trains up to 90 mph.

Additional special provisions for speeds higher than those listed above may be added by the Engineer as necessary.

This chapter is presented as a consensus document by a committee composed of railroad industry professionals having substantial and broad-based experience designing, evaluating, and investigating Concrete Structures and Foundations used by railroads. The recommendations contained herein are based upon past successful usage, advances in the state of knowledge, and current design and maintenance practices. These recommendations are intended for routine use and might not provide sufficient criteria for infrequently encountered conditions. Professional judgment must be exercised when applying the recommendations of this chapter as part of an overall solution to any particular issue.

This chapter is published annually, incorporating revisions made in the previous year. The latest published edition of the chapter should be used, regardless of the age of an existing structure. For purposes of determining historical recommendations under which an existing structure may have been built and maintained, it can prove useful to examine previous editions of the chapter. However, when historical recommendations differ from the recommendations contained in the latest published edition of the chapter, the recommendations of the latest published edition of the chapter should be used.

Part 8, Rigid Frame Concrete Bridges was deleted from the manual in 1975. Part 9, Reinforced Concrete Trestles was deleted from the manual in 1971. Part 15 is reserved for future use. Part 18, Elastomeric Bridge Bearings was moved to Chapter 15 in 2001.

¹ The material in this and other chapters in the AREMA *Manual for Railway Engineering* is published as recommended practice to railroads and others concerned with the engineering, design and construction of railroad fixed properties (except signals and communications), and allied services and facilities. For the purpose of this Manual, RECOMMENDED PRACTICE is defined as a material, device, design, plan, specification, principle or practice recommended to the railways for use as required, either exactly as presented or with such modifications as may be necessary or desirable to meet the needs of individual railways, but in either event, with a view to promoting efficiency and economy in the location, construction, operation or maintenance of railways. It is not intended to imply that other practices may not be equally acceptable.

TABLE OF CONTENTS

Part/Section	Description	Page
1	Materials, Tests and Construction Requirements	8-1-1
1.1	General	8-1-6
1.2	Cement	8-1-8
1.3	Other Cementitious Materials	8-1-10
1.4	Aggregates	8-1-11
1.5	Water	8-1-16
1.6	Reinforcement	8-1-16
1.7	Concrete Admixtures	8-1-19
1.8	Storage of Materials	8-1-20
1.9	Forms	8-1-21
1.10	Details of Reinforcement	8-1-24
1.11	Concrete Jointing	8-1-27
1.12	Proportioning	8-1-31
1.13	Mixing	8-1-37
1.14	Depositing Concrete	8-1-39
1.15	Depositing Concrete Under Water	8-1-43
1.16	Concrete in Sea Water	8-1-46
1.17	Concrete in Alkali Soils or Alkali Water	8-1-46
1.18	Curing	8-1-48
1.19	Formed Surface Finish	8-1-51
1.20	Unformed Surface Finish	8-1-51
1.21	Decorative Finishes	8-1-52
1.22	Penetrating Water Repellent Treatment of Concrete Surfaces	8-1-52
1.23	Repairs and Anchorage Using Reactive Resins	8-1-55
1.24	High Strength Concrete (1995)	8-1-56
1.25	Specialty Concretes	8-1-57
1.26	Self-Consolidating Concrete	8-1-63
1.27	Cathodic Protection	8-1-65
	Commentary	8-1-67
2	Reinforced Concrete Design	8-2-1
2.1	General	8-2-5
2.2	Notations, Definitions and Design Loads	8-2-9
2.3	Materials	8-2-21
2.4	Hooks and Bends	8-2-22
2.5	Spacing of Reinforcement (2005)	8-2-23
2.6	Concrete Protection for Reinforcement	8-2-23
2.7	Minimum Reinforcement of Flexural Members (1992)	8-2-24
2.8	Distribution of Reinforcement in Flexural Members (2005)	8-2-24
2.9	Lateral Reinforcement of Flexural Members (2005)	8-2-25
2.10	Shear Reinforcement – General Requirements	8-2-25
2.11	Limits for Reinforcement of Compression Members	8-2-26
2.12	Shrinkage and Temperature Reinforcement (2005)	8-2-28
2.13	Development Requirements (2017)	8-2-28
2.14	Development Length of Deformed Bars and Deformed Wire in Tension (2019)	8-2-30
2.15	Development Length of Deformed Bars in Compression (2017)	8-2-31
2.16	Development Length of Bundled Bars (2016)	8-2-32
2.17	Development of Standard Hooks in Tension (2019)	8-2-32
2.18	Combination Development Length	8-2-33

TABLE OF CONTENTS (CONT)

Part/Section	Description	Page
2.19	Development of Welded Wire Reinforcement in Tension	8-2-33
2.20	Development of Headed and Mechanically Anchored Deformed Bars in Tension (2019)	8-2-34
2.21	Anchorage of Shear Reinforcement (2017)	8-2-35
2.22	Splices of Reinforcement	8-2-36
2.23	Analysis Methods	8-2-39
2.24	Design Methods (1992)	8-2-44
2.25	General Requirements (1992)	8-2-45
2.26	Allowable Service Load Stresses	8-2-45
2.27	Flexure (2005)	8-2-46
2.28	Compression Members with or without Flexure (1992)	8-2-47
2.29	Shear	8-2-47
2.30	Strength Requirements	8-2-55
2.31	Design Assumptions	8-2-55
2.32	Flexure	8-2-56
2.33	Compression Members with or without Flexure	8-2-59
2.34	Slenderness Effects in Compression Members	8-2-61
2.35	Shear	8-2-63
2.36	Permissible Bearing Stress (2005)	8-2-70
2.37	Serviceability Requirements	8-2-71
2.38	Fatigue Stress Limit for Reinforcement (2005)	8-2-71
2.39	Distribution of Flexural Reinforcement (2005)	8-2-71
2.40	Control of Deflections	8-2-72
	Commentary	8-2-72
3	Spread Footing Foundations	8-3-1
3.1	General	8-3-2
3.2	Information Required	8-3-3
3.3	Depth of Base of Footings	8-3-6
3.4	Sizing of Footings	8-3-7
3.5	Footings with Eccentric Loads	8-3-12
3.6	Footing Stresses	8-3-14
3.7	Field Conditions	8-3-14
3.8	Combined Footings	8-3-15
4	Pile Foundations	8-4-1
4.1	General	8-4-2
4.2	Design	8-4-4
4.3	Pile Length Determination	8-4-7
4.4	Pile Structural Design	8-4-10
4.5	Installation of Piles	8-4-15
4.6	Inspection of Pile Driving	8-4-18
	Commentary	8-4-18
5	Retaining Walls, Abutments and Piers	8-5-1
5.1	Definitions	8-5-2
5.2	Information Required	8-5-4
5.3	Computation of Applied Forces	8-5-5
5.4	Stability Computation	8-5-7
5.5	Design of Backfill	8-5-8

TABLE OF CONTENTS (CONT)

Part/Section	Description	Page
5.6	Designing Bridges to Resist Scour	8-5-9
5.7	Details of Design and Construction for Abutments and Retaining Walls	8-5-11
5.8	Details of Design and Construction for Bridge Piers	8-5-12
6	Crib Walls	8-6-1
6.1	General	8-6-2
6.2	Design of Crib Walls	8-6-2
6.3	Requirements for Reinforced Concrete Crib Walls	8-6-3
6.4	Requirements for Metal Crib Walls	8-6-5
6.5	Requirements for Timber Crib Walls	8-6-6
7	Mechanically Stabilized Embankment	8-7-1
7.1	General	8-7-2
7.2	Design of Mechanically Stabilized Embankments	8-7-2
7.3	Construction	8-7-3
10	Reinforced Concrete Culvert Pipe	8-10-1
10.1	General	8-10-2
10.2	Materials	8-10-6
10.3	Design	8-10-6
10.4	Installation	8-10-13
	Commentary	8-10-17
11	Lining Railway Tunnels	8-11-1
11.1	General	8-11-2
11.2	Design	8-11-2
11.3	Forms	8-11-7
11.4	Concrete	8-11-8
12	Cantilever Poles	8-12-1
12.1	General	8-12-2
12.2	Materials	8-12-2
12.3	Construction	8-12-2
12.4	Design	8-12-3
14	Repair and Rehabilitation of Concrete Structures	8-14-1
14.1	Scope (2017)	8-14-3
14.2	Determination of the Causes of Concrete Deterioration (2017)	8-14-3
14.3	Evaluation of the Effects of Deterioration and Damage (2017)	8-14-4
14.4	Principal Materials Used in the Repair of Concrete Structures	8-14-5
14.5	Repair Methods (2017)	8-14-7
14.6	Repair Methods for Prestressed Members	8-14-23
	Commentary	8-14-25
16	Design and Construction of Reinforced Concrete Box Culverts	8-16-1
16.1	General	8-16-2
16.2	Materials	8-16-4
16.3	Design Methods	8-16-6
16.4	Design Loads	8-16-6

TABLE OF CONTENTS (CONT)

Part/Section	Description	Page
16.5	Details of Design	8-16-13
16.6	Manufacture of Precast Units	8-16-15
16.7	Construction	8-16-17
17	Prestressed Concrete	8-17-1
17.1	General Requirements and Materials	8-17-4
17.2	Notations (2014)	8-17-5
17.3	Terms (2014)	8-17-7
17.4	Materials	8-17-9
17.5	Details of Prestressing Tendons and Ducts	8-17-11
17.6	General Analysis (2014)	8-17-13
17.7	Expansion and Contraction (2014)	8-17-13
17.8	Span Length (2014)	8-17-13
17.9	Frames and Continuous Construction	8-17-14
17.10	Effective Flange Width	8-17-15
17.11	Flange and Web Thickness-Box Girders (2014)	8-17-15
17.12	Diaphragms (2014)	8-17-16
17.13	Deflections (2014)	8-17-16
17.14	General Design	8-17-17
17.15	Load Factors	8-17-18
17.16	Allowable Stresses	8-17-18
17.17	Loss of Prestress	8-17-20
17.18	Flexural Strength	8-17-26
17.19	Ductility Limits	8-17-28
17.20	Non-Prestressed Reinforcement (2014)	8-17-29
17.21	Shear	8-17-30
17.22	Post-Tensioned Anchorage Zones	8-17-34
17.23	Pretensioned Anchorage Zones (2014)	8-17-44
17.24	Concrete Strength at Stress Transfer (2014)	8-17-45
17.25	General Detailing	8-17-45
17.26	General Fabrication	8-17-48
17.27	Mortar and Grout	8-17-52
17.28	Application of Loads (2014)	8-17-52
17.29	Materials - Reinforcing Steel	8-17-53
17.30	Prestressed Concrete Cap and/or Sill for Timber Pile Trestle (2014)	8-17-54
	Commentary (2014)	8-17-57
19	Rating of Existing Concrete Bridges	8-19-1
19.1	General	8-19-2
19.2	Rating	8-19-2
19.3	Loads and Forces	8-19-4
19.4	Materials	8-19-5
19.5	Load Combinations and Rating Formulas	8-19-8
19.6	Excessive Loading	8-19-10
	Commentary	8-19-11
20	Flexible Sheet Pile Bulkheads	8-20-1
20.1	General	8-20-2
20.2	Information Required	8-20-3

TABLE OF CONTENTS (CONT)

Part/Section	Description	Page
20.3	Computation of Lateral Forces Acting on Bulkheads	8-20-5
20.4	Stability	8-20-9
20.5	Design of Anchored Bulkheads	8-20-10
20.6	Cantilever Bulkheads	8-20-14
20.7	Notations (1993)	8-20-15
	Commentary	8-20-16
21	Inspection of Concrete and Masonry Structures	8-21-1
21.1	General (2018)	8-21-1
21.2	Reporting of Defects (2018)	8-21-2
21.3	Inspection (2018)	8-21-2
	Commentary	8-21-22
22	Geotechnical Subsurface Investigation	8-22-1
22.1	General (1992)	8-22-2
22.2	Scope (1992)	8-22-2
22.3	Classification of Investigations	8-22-2
22.4	General	8-22-3
22.5	Exploration Methods	8-22-4
22.6	Determination of Groundwater Level (1992)	8-22-6
22.7	Sampling	8-22-6
22.8	Records	8-22-7
22.9	Inspection (1992)	8-22-9
22.10	Geophysical Explorations (1992)	8-22-9
22.11	In-Situ Testing of Soil (1992)	8-22-9
22.12	Backfilling Bore Holes (1992)	8-22-10
22.13	Cleaning Site (1992)	8-22-10
23	Pier Protection Systems at Spans Over Navigable Streams	8-23-1
23.1	General	8-23-2
23.2	Special Considerations	8-23-3
23.3	Design	8-23-4
23.4	Construction	8-23-20
	Commentary (2010)	8-23-24
24	Drilled Shaft Foundations	8-24-1
24.1	General	8-24-2
24.2	Information Required	8-24-5
24.3	Design	8-24-5
24.4	Material	8-24-8
24.5	Construction	8-24-9
24.6	Testing	8-24-12
	Commentary	8-24-12
25	Slurry Wall Construction	8-25-1
25.1	General	8-25-2
25.2	Design	8-25-3
25.3	Materials	8-25-7
25.4	Construction	8-25-9

TABLE OF CONTENTS (CONT)

Part/Section	Description	Page
	Commentary (2012)	8-25-13
26	Recommendations for the Design of Segmental Bridges.....	8-26-1
26.1	General Requirements and Material	8-26-4
26.2	Methods of Analysis	8-26-8
26.3	Design Loads	8-26-12
26.4	Load Factors	8-26-16
26.5	Allowable Stresses	8-26-21
26.6	Prestress Losses (1996).....	8-26-22
26.7	Flexural Strength.....	8-26-23
26.8	Shear and Torsion.....	8-26-23
26.9	Fatigue Stress Limits	8-26-32
26.10	Design of Local and General Anchorage Zones, Anchorage Blisters and Deviation Saddles	8-26-32
26.11	Provisional Post-Tensioning Ducts and Anchorages	8-26-35
26.12	Duct Details	8-26-36
26.13	Couplers (1996)	8-26-38
26.14	Connection of Secondary Beams (1996)	8-26-38
26.15	Concrete Cover and Reinforcement Spacing	8-26-40
26.16	Inspection Access (1996)	8-26-40
26.17	Box Girder Cross Section Dimensions and Details	8-26-40
	Commentary	8-26-41
27	Concrete Slab Track.....	8-27-1
27.1	Scope and Notations	8-27-3
27.2	Application and Definitions	8-27-3
27.3	General Considerations.....	8-27-6
27.4	Materials	8-27-7
27.5	Design.....	8-27-8
27.6	Construction	8-27-10
27.7	Direct Fixation Fastening System.....	8-27-14
27.8	Special Considerations	8-27-16
	Commentary	8-27-24
28	Temporary Structures for Construction.....	8-28-1
28.1	General	8-28-2
28.2	Information Required	8-28-4
28.3	Computation of Lateral Forces (2002) R(2015)	8-28-5
28.4	Stability (2002) R(2015).....	8-28-5
28.5	Design of Shoring Systems.....	8-28-5
28.6	Design of Falsework Systems.....	8-28-13
	Commentary	8-28-18
29	Waterproofing.....	8-29-1
29.1	General Principles.....	8-29-4
29.2	Waterproofing (2001)	8-29-4
29.3	Dampproofing (1994).....	8-29-5
29.4	Specific Application	8-29-5
29.5	Terms (2001).....	8-29-7
29.6	Applicable ASTM Designations	8-29-8

TABLE OF CONTENTS (CONT)

Part/Section	Description	Page
29.7	General Practices	8-29-12
29.8	Primers	8-29-13
29.9	Membranes	8-29-13
29.10	Membrane Protection	8-29-17
29.11	Sealing Compounds for Joints and Edges of Membrane Protection (2001)	8-29-20
29.12	Anti-Bonding Paper (2001)	8-29-20
29.13	Inspection and Tests (1994)	8-29-20
29.14	Construction	8-29-20
29.15	Introduction to Dampproofing	8-29-27
29.16	Materials for Dampproofing	8-29-27
29.17	Application of Dampproofing	8-29-29
	Commentary	8-29-29
Chapter 8 Glossary		8-G-1
References		8-R-1

INTRODUCTION

The Chapters of the AREMA Manual are divided into numbered Parts, each comprised of related documents (specifications, recommended practices, plans, etc.). Individual Parts are divided into Sections by centered headings set in capital letters and identified by a Section number. These Sections are subdivided into Articles designated by numbered side headings.

Page Numbers – In the page numbering of the Manual (8-2-1, for example) the first numeral designates the Chapter number, the second denotes the Part number in the Chapter, and the third numeral designates the page number in the Part. Thus, 8-2-1 means Chapter 8, Part 2, page 1.

In the Glossary and References, the Part number is replaced by either a “G” for Glossary or “R” for References.

Document Dates – The bold type date (Document Date) at the beginning of each document (Part) applies to the document as a whole and designates the year in which revisions were last made somewhere in the document, unless an attached footnote indicates that the document was adopted, reapproved, or rewritten in that year.

Article Dates – Each Article shows the date (in parenthesis) of the last time that Article was modified.

Revision Marks – All current year revisions (changes and additions) which have been incorporated into the document are identified by a vertical line along the outside margin of the page, directly beside the modified information.

Proceedings Footnote – The Proceedings footnote on the first page of each document gives references to all Association action with respect to the document.

Annual Updates – New manuals, as well as revision sets, will be printed and issued yearly.